Detailed Estimate Local Government Engineering Department

Scheme Code : 47588-21-10002 Scheme Preparation Date : 18-Jul-2021

Road Code : 47588

FY & Type of Rate : 2019-2020 (General)

Financial Year : 2020-2021

District : NOAKHALI Upazila : SONAIMURI

	Name	of the	Scheme	:
--	------	--------	--------	---

SL	Item Code	Description of Work	Unit	Location /	Length	Width	Height /	Area /	No of	Total Qty	Unit	Amount
No		·		Component	_		Depth	Volume	Item	of Works	Rate	
		•		-		_			4.0		4.0	4.0

	No				Component			Depth	Volume	Item	of Works	Rate	
Ī	1	2	3	4	5	6	7	8	9	10	11	12	13
-	1.	14.01.02	Drinking Water Facilities: Providing continuous adequate drinking water supply at worksite and site office as well by installing necessary tube-well/s where applicable or any other means depending on local situation, also providing essential arrangement for storing drinking water by supplying portable best quality water tank equivalent to Gazi/Padma of adequate capacity depending on the number of users, including supplying 1 (one) no. best quality water filter of minimum capacity 30 liters with necessary kits, etc. all complete as per satisfaction and direction of the Engineer-in-charge, all relevant goods and equipment under this item shall be property of the contractor and payment will be made after 100% completion of the contract successfully.	LS						1.00		5000	5000.00
2	2.	14.01.03	Temporary Toilet Facilities: Providing at least two nos. portable toilets or constructing temporary semi pucca toilets with two pit latrine one for female worker and another for male worker at worksite and workers accommodation site in a safe location, so that no adverse impact will generate	LS						2.00		5000	10000.00

portable toilets or constructing temporary semi pucca toilets with two pit latrine one for female worker and another for male worker at worksite and workers accommodation site in a safe location, so that no adverse impact will generate on the surrounding environment, including providing requisite arrangement for water supplying etc. All complete as per drawing, specification, direction and satisfaction of the Engineer-in-charge. All relevant accessories and arrangements under this item shall be property of the contractor and payment will be made after 100% completion of the contract successfully.

Scheme Code : 47588-21-10002; October, 2019 Print Date/Time: 18-Jul-2021 08:18 PM Page 1

SL No	Item Code	Description of Work	Unit	Location / Component	Length	Width	Height / Depth	Area / Volume	No of Item	Total Qty of Works	Unit Rate	Amount
1	2	3	4	5	6	7	8	9	10	11	12	13
3.	14.02.03	Waste Disposal Facilities: Providing, installing and maintaining at least 2 (two) nos. waste collection bins one for organic waste and other for inorganic waste of minimum capacity of 30liters with hinge supported 450mm dia cover plate for opening, made of durable plastic material at worksite, both bins will be kept in a safe and easily accessible place, so that will easy to use and no adverse impact will generate on the surrounding environment, including continuing the full functioning of waste disposal(buried/incineration) in accordance with the full satisfaction of the project manager throughout the contract period, all complete as per drawing, specification and direction of the Engineer-in-charge. Entire relevant accessories and arrangements under this item shall be property of the contractor and payment will be made after 100% completion of the contract successfully.	LS						1.00		5000	5000.00
4.	14.03.01	Control of Water Pollution: Providing necessary arrangement to prevent entrance, or accidental spillage, solid matter, contaminants, debris, garbage, cement, concrete, sanitary waste, oil, other petroleum products, pollutants and wastewaters from aggregate processing, concrete batching, or other construction operations into streams, flowing or dry watercourses, lakes, and underground water sources for ensuring water quality, including monitoring pH value, dissolved oxygen (DO), biochemical oxygen demand (BOD), chemical oxygen demand (COD), total dissolved solids (TDS), etc, including concerned tests to be carried out three times (before, during and end of physical work) from any laboratories approved by PM, all complete as per requirement and full satisfaction of Engineer-in-charge. Payment will be made after 100% completion of the contract successfully.	LS						3.00		5000	15000.00
5.	14.03.02	Control of Air Pollution (Dust Suppression): Maintaining, carrying out proper and efficient measures wherever and as often as necessary to reduce dust nuisance, and to prevent dust which has originated from contractor's activities/ operations at the worksite and site office, including sprinkling water on aggregates/unpaved roads at least three times a day or more depending on the atmospheric conditions, including keeping necessary covering/protection on stockpiled fine aggregates to reduce dust nuisance during natural air blowing, all complete like emission of dust into the atmosphere shall be strictly controlled during manufacture, handling, storage of concrete, road aggregates, and to be used such methods and equipment as are necessary for collection and disposal, or prevention, of dust during these operations means of eliminating atmospheric discharges of dust as per requirement and carrying out air quality test as PM10, PM25, SPM, NOx, Sox as per instruction of Engineer-incharge. Payment will be made after 100% completion of the contract successfully.	LS						1.00		8000	8000.00

 Scheme Code : 47588-21-10002; October, 2019
 Print Date/Time: 18-Jul-2021 08:18 PM
 Page 2

SL No	Item Code	Description of Work	Unit	Location / Component	Length	Width	Height / Depth	Area / Volume	No of Item	Total Qty of Works	Unit Rate	Amount
1	2	3	4	5	6	7	8	9	10	11	12	13
6.	14.03.03	Control of Soil Pollution: Providing appropriate controlling measures to prevent entrance, or accidental spillage, solid matter, contaminants, debris, garbage, cement, concrete, sanitary waste, oil, other petroleum products and wastes into soil to avoid soil pollution at worksite and to evade emission of high concentration of sediments into wetlands, swampy areas and other particular sensitive areas, all complete as per requirement and full satisfaction of Engineer-in-charge. Payment will be made after 100% completion of the contract	LS						1.00		5000	5000.00
7.	14.04.02	Traffic Management: Maintaining traffic management at worksite from time of commencement of contractor's activities to time of completion activities, including ensuring that the road is safe for users, providing a safe working area for those involved in work on trafficked network and minimizing any disruption to smooth flow of traffic (this includes providing necessary barricades, warning signs/lights, guide signs, flagmen, maintaining diversion roads by cutting, filling, constructing, etc. or by any other means) in accordance with the full satisfaction of the Engineering-in-charge, unless specified otherwise, including keeping provision for existing traffic and pedestrian movements in such a way as to assure that a single lane at least 3.0m wide is available for public traffic at all times (including access to properties and local roads) affected by the contractor's activities shall be maintained at all times (day & night), including removal of all temporary constructions on completion of the activities, etc. all complete as per requirement and instruction of Engineer-incharge. All relevant accessories and arrangements under this item shall be property of the contractor and payment will be made after 100% completion of the contract	LS						1.00		7000	7000.00
8.	M.M-01	Sign Board: Providing, erecting and fixing construction signboardof size 1.7mx1.2m made of MS (20BWG) sheet fixed over a frame, suported on suitable bambo post firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45x45x90cm below ground level as per approved drawing and specifications in/c two coats of painting with best quality synthetic anamel paint of approved brand & painted by approved firm of sign writers in accordance with the detailes shown on the drawing etc. signboard should be sound & weather proof construction, all complete in all respect as per approved drawing and direction of the Engineer -in-charge. Rate is inclusive of cost of all materials, labour and all incidental charges in this connection.	LS						1.00 TO	TAL SCHEME A	5000	5000.00
											SAY:	60,000.00

Scheme Code: 47588-21-10002; October, 2019 Print Date/Time: 18-Jul-2021 08:18 PM

Page 3

In Word: Taka (Sixty Thousand) Only

(Md Anwar Pervez) Executive Engineer LGED, NOAKHALI (Md. Ekramul Haque) Executive Engineer LGED, NOAKHALI